

GOLDEN VALLEY RANCH REGIONAL ROADWAY IMPROVEMENTS

BUDGET COST ESTIMATE

ROADWAY NO. S30: INDIAN WELLS ROAD FROM AQUARIUS DRIVE TO HOLY MOSSES WASH

NEW COST CODE	DESCRIPTION	UNIT	UNIT COST	QUANTITY	TOTAL
2-12-0200	AGGREGATE BASE	CY	\$ 48.00	4,541.00	\$ 217,968.00
2-12-0200	ASPHALT CONCRETE PAVEMENT, 5-INCH	SY	\$ 13.00	14,862.00	\$ 193,206.00
2-13-0200	CONCRETE CURB AND GUTTER, TYPE A	LF	\$ 8.25	5,350.00	\$ 44,137.50
2-13-0200	CONCRETE VALLEY GUTTER, 6-INCH, 3 FEET	SF	\$ 6.00	240.00	\$ 1,440.00
2-13-0400	CONCRETE SIDEWALK, 4-INCH, 5 FEET	SF	\$ 3.50	26,750.00	\$ 93,625.00
2-13-0300	BRIDGE STRUCTURE	SF	\$ 85.00	3,200.00	\$ 272,000.00
2-09-0400	6-INCH PVC WATER MAIN	LF	\$ 20.00	120.00	\$ 2,400.00
2-09-0400	8-INCH PVC WATER MAIN	LF	\$ 40.00	60.00	\$ 2,400.00
2-09-0400	12-INCH PVC WATER MAIN	LF	\$ 60.00	2,675.00	\$ 160,500.00
2-09-0400	FIRE HYDRANT ASSEMBLY	EA	\$ 2,000.00	6.00	\$ 12,000.00
2-09-0200	8-INCH SEWER PIPE	LF	\$ 15.00	60.00	\$ 900.00
2-09-0200	12-INCH SEWER PIPE	LF	\$ 20.00	2,675.00	\$ 53,500.00
2-09-0200	SEWER MANHOLE, 48 INCH	EA	\$ 5,000.00	6.00	\$ 30,000.00
2-10-0500	CONDUIT, PVC, 6 IN. (ELECTRIC)	LF	\$ 7.50	8,025.00	\$ 60,187.50
2-10-0500	MANHOLE, ELECTRIC	EA	\$ 5,000.00	6.00	\$ 30,000.00
2-10-0400	CONDUIT, PVC, 4 IN. (TELEPHONE)	LF	\$ 7.50	10,700.00	\$ 80,250.00
2-10-0400	MANHOLE, TELEPHONE	EA	\$ 5,000.00	6.00	\$ 30,000.00
2-10-0600	CONDUIT, PVC, 3 IN. (CABLE)	LF	\$ 6.00	2,699.00	\$ 16,194.00
2-10-0600	PULL BOX, CABLE	EA	\$ 900.00	3.00	\$ 2,700.00
2-15-0400	TRAFFIC SIGNS WITH METAL SUPPORTS	EA	\$ 100.00	12.00	\$ 1,200.00
2-10-0200	NO. 3-1/2 PULL BOX	EA	\$ 500.00	4.00	\$ 2,000.00
2-10-0200	UNDERGROUND ELECTRICAL SERVICE	EA	\$ 1,500.00	1.00	\$ 1,500.00
2-10-0200	WIRE, 2/C NO. 4 & 1/C NO. 8 COPPER IN 1-1/4-INCH PVC CONDUIT	LF	\$ 3.00	5,500.00	\$ 16,500.00
2-10-0200	STREET LIGHT ASSEMBLY	EA	\$ 3,000.00	32.00	\$ 96,000.00
2-15-0400	PAVEMENT STRIPING	LF	\$ 1.00	12,000.00	\$ 12,000.00
2-15-0400	PAVEMENT MESSAGE MARKINGS	EA	\$ 100.00	24.00	\$ 2,400.00
SUBTOTAL					\$ 1,435,008.00
ENGINEERING & SURVEY @				15.00%	\$ 215,251.20
TOTAL					\$ 1,650,259.20

[illegible]